

The School District of Newberry County is accepting proposals for the following work at Newberry County Career Center and Mid-Carolina Middle School.

Career Center Location:  
3414 Main St  
Newberry, SC 29108

Mid-Carolina Middle School Location:  
6794 US Highway 76  
Prosperity, SC 29127

Proposals must be in writing and submitted to the Technology Department on or before Friday, December 3, 2010. They may be emailed, mailed, or hand delivered to:

Tina Palmer (tpalmer@newberry.k12.sc.us)  
PO Box 718  
Newberry, SC 29108

Please email or call Tina at 803.321.2660 to schedule a walk-thru of the buildings.

***Description of work***

The scope of work for this project consists of the installation of Cat5e cabling for an IP camera system, installation of IP cameras, power injectors if necessary, running of all necessary conduits, installation of ExacqVision software on vendor provided camera server, and all necessary software/licenses for cameras and server. Axis is the preferred IP camera.

Vendor must be an authorized reseller of the IP cameras proposed and be certified to install and maintain the proposed cameras. Vendor must provide a letter from the manufacturer (on the manufacturers letterhead) stating that they are currently in good standing and meet the requirements listed above. All IP cameras must come with a minimum of a 3 years manufacturer's warranty with advanced replacement.

All copper connectivity will be rated for Category 5e performance. All cables will be tested and labeled to comply with BICSI standards and submitted to the cable manufacturer for the PCI 25 year warranty. Patch cables will need to be provided. Contractor will need to run Cat5e cables/drops for cameras (in conduit where necessary).

Furnish, install, and configure 1 rack-mount Video Recording server with ExacqVision server software. VMS licensing software required. Minimum server requirements: dual core processor, 4 GB RAM, 2 TB of storage with an 80GB HD for OS Partition. Operating System shall be 32 bit Windows platform.

NCCC: There will be approximately 7-10 IP cameras/cables installed in the building(s) and 6-10 outside cameras.

MCMS: There will be approximately 28-30 IP cameras/cables installed in the building(s) and 14-16 outside cameras.

\*\* Contractor will provide cable, conduit where necessary, patch panels, video server, and cameras.